LUNCH ROOM
118

SEE SHT. A-3 FOR INTERIOR ELEV.

REF. SEE SPEC.

TOP OF RADIATOR GRILLE
EXTEND BENCH 6" PAST RADIATOR GRILLE

4" SOUND INSULATION
SELECT BOARD ROOM ONLY

SELECT BOARD ROOM
107

MEETING HALL
102

LISTER
116

PROVIDE 4" SLAB ON 12" COMPACTED GRAVEL (6" WIDER THAN MECH. UNIT)

LIMITED AREA SPRINKLER

MECHANICAL
119

4" SOUND INSULATION
CONT. IN THIS WALL
(LENGTH OF MTG. HALL)

BUILT-IN BENCH (SEE DETAIL SHT. A-5)

FILES
117

MEN
115

WOMEN
114

5" TURNING RADIUS TO TO CLEAR EDGE OF TOILET

2x6 FRAMED FINWALLS (TYP.)

SEE SHT. A-3 FOR INT. ELEV. OF MEN AND WOMEN

LIMITED AREA SPRINKLER

FILES
111

CORRIDOR
112

4" HIGH WALL

STOR.
113

TO FAN ROOM

F.E.C.

CUPOLA ABOVE
SEE DET. ON SHT. A-5

CARP

VCT

ABOVE VAULT

FILES
106

HOLLOW METAL FRAME
2'-8" x 6'-8"

VAULT
108

NOTE: SEE DET #4, SHT. A-5 FOR WALL / CEILING DETAIL FOR VAULT

WORK AREA
109

HOLLOW METAL FRAME
5'-0" x 6'-8"

STAIR
120

BOXED WOOD STAIRS
5 / 4 TREADS, 14 RISERS, CARPET GRADE.
"BROSCO" 75 HANDRAIL W/ BRACKETS (BOTH SIDES)
AT 34" ABOVE LEADING EDGE OF TREAD

HARDWOOD CAP ON LOW WALL

OFFICE
110

ZONING AND PLANNING
109

VESTIBULE
100

+ ELEV. 253'-0"

+ ELEV. 252'-11 3/4"

+ ELEV. 252'-11"

+ ELEV. 252'-0"

TOWN CLERK
105

OFFICE
104

2'-0" WIDE x 3'-8" HIGH WINDOWS IN HOLLOW MET. FRAMES

3' WIDE x 3'-8" HIGH WINDOW IN HOLLOW MET. FRAME

6" BATT INSULATION

EXTEND WALL TO CEILING OF FAN ROOM TYP.

WALLS AND CEILING TAPED AND SPACKELED - NO PAINT

ATTIC STORAGE
121

INSULATE CEILING R-38, RATE ONE HOUR TWO LAYERS 5/8" FIRECODE SEPARATED

+ ELEV. 262'-6"

RATED FLOOR ASSEMBLY PER U.L. DES. #L501 SYSTEM ONE - TWO LAYERS PLYWOOD

1 1/2" DIA. PTD. MET. PIPE RAIL
THICKEN SLAB TO 6" AT EACH VERT. POST
SEE ELEVATION FOR CONFIGURATION

RAMP

SEE SHT. L-1 FOR LANDSCAPING

CONCRETE SIDEWALK SEE SHT. L-1 FOR DETAIL

GENERAL NOTES:

1. ALL EXTERIOR WALLS ARE WALL TYPE # 1.
2. INTERIOR WALLS ARE WALL TYPE # 2 UNLESS OTHERWISE INDICATED BY A WALL TYPE SYMBOL.
3. ALL DOORS ARE TO HAVE CLEARANCES TO MEET HANDICAPPED CODES.
4. ALL INTERIOR PARTITIONS ARE TO EXTEND TO STRUCTURE ABOVE.
5. IF ANY INFORMATION IS UNCLEAR, CONTACT THE ARCHITECT IMMEDIATELY FOR CLARIFICATION.
6. MECHANICALLY FASTEN ALL INTERIOR PARTITIONS TO SLAB. (MIN. 6'-0" O.C. AND MIN. 2 PER PARTITION WALL)