

MOUND CONSTRUCTION

***PRIOR TO CONSTRUCTION ALL MATERIALS SHALL BE APPROVED BY THE DESIGNER

THE FOLLOWING IS THE PROCEDURE FOR MOUND CONSTRUCTION AND VARIATIONS SHOULD BE DISCUSSED WITH THE DESIGNER BEFORE ANY MOUND CONSTRUCTION STARTS. MOUND FAILURE MAY RESULT FROM IMPROPER CONSTRUCTION METHODS AND PROCEDURES. PROPER EQUIPMENT IS ESSENTIAL. SMALL TRACK TYPE DOZERS OR EXCAVATORS WORK BEST. WHEEL TYPE TRACTORS MAY COMPACT THE SUBSOIL.

CONSTRUCTION ON WET SOIL CAUSES SOIL SMearing AND COMPACTION AND POSSIBLE FUTURE FAILURES. CONSTRUCTION SHOULD ONLY BE DONE DRY WEATHER FROM JUNE - NOVEMBER. CONDITIONS PERMITTING AND AVOIDING NO CONSTRUCTION DURING FREEZING TEMPERATURES.

1. PREPARE ENTIRE AREA TO BE COVERED BY MOUND FILL. CUT TREES TO GROUND LEVEL. DO NOT REMOVE STUMPS. MOW VEGETATION AND LEAVES. SITE MUST BE DRY BEFORE FLOWING.

2. PLOW ENTIRE AREA TO BE COVERED BY MOUND FILL. PLOW ALONG THE CENTER OF THE SLOPE WITH A MOUND BREAKER FIVE FEET DEPTH OF 4". THROWING THE SOIL UP SLOPE. PLACEMENT OF THE FILL ON FLOWED AREA IMMEDIATELY AFTER FLOWING IS REQUIRED. DO NOT LEAVE FLOWED AREA TO RUN IN. KEEP ALL TRAFFIC OFF FLOWED AREA DOWNSLOPE SIDE OF FLOWED AREA.

3. PLACE APPROVED SAND FILL AROUND THE UPHILL AND SIDE EDGES OF THE FLOWED AREA. KEEP WHEELS OR TRACKS OFF FLOWED AREA. NO TRAFFIC DOWNSLOPE SIDE OF FLOWED AREAS. WORK FROM ENDS AND UPSLOPE SIDE ONLY.

4. MOVE THE SAND FILL INTO PLACE USING A SMALL TRACK TYPE DOZER. ALWAYS KEEP AT LEAST 6" OF SAND BENEATH TRACKS TO PREVENT COMPACTION OF THE FLOWED AREA. PLACE SAND FILL TO THE REQUIRED DEPTH.

5. PLACE PRESBY PIPE AS SHOWN ON DETAILS FILL WITH MOUND SAND BETWEEN PIPES. COVER PIPE WITH FILTER FABRIC:

6. PLACE 6" OF SUBSOIL OR TOPSOIL (SOIL LESS PERMEABLE THAN SAND FILL) OVER ALL SAND. (INCREASE DEPTH TO 12" OVER TOP CENTER OF MOUND IN PLACE.) 6" OF SAND OR QUALITY TOPSOIL OVER ENTIRE MOUND SURFACE. SOIL MAY BE TAKEN FROM EXISTING OR NEW SOIL. BUT NOT FROM WITHIN 50' DOWNHILL OF MOUND OR FROM REPLACEMENT AREA.

7. SEED AND MULCH ENTIRE MOUND SURFACE IMMEDIATELY TO PREVENT EROSION.

INSPECTION

1. THE SYSTEM MUST BE INSPECTED BY HIGH KNOB DESIGN ASSOCIATES LLC TO ENSURE COMPLIANCE WITH THE NEW VERMONT HIGH KNOB DESIGN ASSOCIATES LLC ASSUMES NO RESPONSIBILITY AND LIABILITY FOR PROBLEMS THAT ARISE FROM FAILURE TO FOLLOW THE PLAN AND SPECIFICATIONS AND FAILURE TO HAVE BEEN NOTIFIED BY THE CONTRACTOR FOR THE REQUIRED INSPECTIONS DURING CONSTRUCTION.

2. THE CONTRACTOR SHALL NOTIFY HIGH KNOB DESIGN ASSOCIATES LLC A MINIMUM OF 72 HOURS IN ADVANCE FOR THE FOLLOWING INSPECTIONS:

A) THE FLOWED EXISTING GROUND PRIOR TO PLACEMENT OF SAND FILL

B) THE DISTRIBUTION BOX SYSTEM

C) FINAL GRADING AND SEEDING

THE DESIGNER HAS DETERMINED A LOCATION FOR ON-SITE WASTEWATER DISPOSAL ON THE PROPERTY BASED ON A SITE EVALUATION AND SOIL TEST PITS. IT WAS DETERMINED THAT THE PROPOSED LOCATION WAS THE BEST LOCATION AVAILABLE. THE OWNER IS RESPONSIBLE FOR PROPER OPERATION AND MAINTENANCE OF THE PROPOSED SYSTEM TO PROTECT PUBLIC HEALTH AND THE GROUNDWATER.


1. RECOMMEND CHECKING THE LEVELS OF SOLIDS IN THE SEPTIC TANK ON A YEARLY BASIS AND PUMPED AS NEEDED. THE EFFLUENT FILTER SHOULD BE CHECKED AND CLEANED AT THE SAME TIME. THE PUMP STATION SHOULD ALSO BE CHECKED FOR SOLIDS. ALL SOLIDS SHOULD BE REMOVED WHEN FOUND IN THE PUMP STATION.

THE LIFE OF THE SYSTEM CAN NOT BE ESTIMATED DUE TO CONDITIONS BEYOND THE CONTROL OF THE DESIGNER SUCH AS MONITORING OF FOREIGN MATERIAL INTO THE SYSTEM (USE OF NON-Biodegradable Detergents, Chemicals) WILL ADVERSELY AFFECT THE OPERATION OF THE DISPOSAL SYSTEM.


GARBAGE DISPOSALS AND WATER SOFTENERS ARE NOT ALLOWED.

1. RECOMMEND INSTALLING WATER SAVING FIXTURES AND CONSERVING WATER WHENEVER POSSIBLE.


DUE TO INSTANCES BEYOND THE DESIGNER'S CONTROL THE DESIGNER ASSUMES NO RESPONSIBILITY FOR THE CONTINUED FUNCTIONING AND PROPER USE AND MAINTENANCE OF THE SYSTEM.





WELL CONSTRUCTION DETAIL




Absorption Trench Plan Lot 2



Absorption Trench Elevation Lot 2



PRESBY MOUND CROSS SECTION LOT 3




PRESBY MOUND LAYOUT

SAND FILL SPECIFICATIONS


SIEVE NO.	OPENING (MM)	PERCENT PASSING BY WEIGHT
10	2.000	85-100
40	0.420	25-75
60	0.250	0-30
100	0.149	0-10
200	0.074	0-5

SIEVE NO.	OPENING (MM)	PERCENT PASSING BY WEIGHT
4	4.750	95-100
8	2.360	80-100
16	1.190	50-85
30	0.950	35-60
50	0.297	10-30
100	0.149	2-10


SIEVE NO.	OPENING (MM)	PERCENT PASSING BY WEIGHT
10	2.000	85-100
40	0.420	30-50
200	0.074	0-10




RAISED CONNECTION DETAIL



PRESBY PIPE CROSS SECTION



FORCE MAIN DETAIL



8-OUTLET ROUND DISTRIBUTION BOX

DATE	DESCRIPTION	BY

THIS DESIGN IS PROPOSED TO SATISFY CRITERIA AND MEET THE INTENT OF THE VERMONT ENVIRONMENTAL PROTECTION RULES CHAPTER 1 WASTEWATER SYSTEM AND POTABLE WATER SUPPLY RULES EFFECTIVE SEPTEMBER 26, 2008.



DETAILS

DIKE PROPERTY
GUINEA ROAD
CHARLOTTE, VERMONT

HIGH KNOB ASSOCIATES LLC

WATER & WASTEWATER DESIGNS
 TOPOGRAPHIC SITE PLANS & MAPPING
 STATE & LOCAL PERMITTING

991 BIG HOLLOW ROAD
 STARKSBORO, VERMONT 05487
 453-9071

DATE	
REV	